

A/ TERMS AND CONDITIONS TO USE

GENERAL

THESE DRAWINGS HAVE BEEN PRODUCED FOR THE SOLE USE OF THE PROJECT CLIENT. THEIR APPOINTED AGENTS, ARCHITECTS, CONSULTANTS AND CONTRACTORS, BY THE USE OF THESE DRAWINGS AND SPECIFICATION BY THE AFOREMENTIONED FIRMS AND INDIVIDUALS, THEY ACKNOWLEDGE AND AGREE TO THE TERMS AND CONDITIONS OF USE AS NOTED BELOW.

THESE STRUCTURAL DRAWINGS AND SPECIFICATIONS HAVE BEEN PREPARED TO ILLUSTRATE THE STRUCTURAL DESIGN PHILOSOPHY AND INTENT. AS SUCH, THESE DRAWINGS PERTAIN SOLELY TO THE "BUILDING STRUCTURE" AND DO NOT ATTEMPT TO DEPICT, DETAIL OR DESIGN ELEMENTS OF THE FINISHED BUILDING DESIGN WHICH ARE THE RESPONSIBILITY OF OTHER DESIGN DISCIPLINES.

STRUCTURAL BUILDING FRAMEWORK

THESE STRUCTURAL DRAWINGS DESCRIBE THE STRUCTURAL BUILDING FRAMEWORK ONLY. THE STRUCTURAL FRAMEWORK IS DEFINED AS THE PRIMARY GRAVITY AND LATERAL LOAD RESISTING ELEMENTS OF THE BUILDING AND INCLUDES THE FOLLOWING ITEMS WHICH MAY OR MAY NOT PERTAIN TO THIS SPECIFIC PROJECT.

- REINFORCED CONCRETE ELEMENTS WHICH COMPRISE THE PRIMARY LOAD CARRYING FRAMEWORK FOR THE BUILDING
- COMPOSITE OR NON-COMPOSITE ROOF OR FLOOR METAL DECKING
- STRUCTURAL STEEL ELEMENTS AS DEFINED BY THE CISC CODE OF STANDARD PRACTICE
- STEEL JOISTS, PRE-CAST CONCRETE SLABS, BEAMS COLUMNS OR WALL ELEMENTS

PROVISION HAS BEEN MADE WITHIN THE DESIGN OF THE STRUCTURAL BUILDING FRAMEWORK TO SUPPORT THE LOADS ARISING FROM NON-STRUCTURAL ELEMENTS. SUCH NON-STRUCTURAL ELEMENTS MAY RELY UPON THE STRUCTURAL BUILDING FRAMEWORK FOR THEIR ULTIMATE SUPPORT. HOWEVER, THE DESIGN, SUPPLY AND INSTALLATION OF SAID SUPPORT MECHANISMS ARE THE RESPONSIBILITY OF THE SPECIFIC ARCHITECTURAL OR SERVICE TRADE AND/OR OTHER ENGINEERING DISCIPLINE.

SPECIFIC ARCHITECTURAL AND SERVICE ELEMENTS MAY RELY UPON THE STRUCTURAL BUILDING FRAMEWORK FOR ULTIMATE SUPPORT YET WHOSE DESIGN AND CONTRACTUAL RESPONSIBILITY DOES NOT LIE WITH THE STRUCTURAL DESIGNER. THE DESIGNER AND/OR PROVIDERS OF THE FOLLOWING ELEMENTS, ARE WHOLLY RESPONSIBLE FOR DELIVERING THEIR LOADS TO THE STRUCTURE AS DEFINED BY THESE DRAWINGS:

- EXTERIOR BUILDING CLADDING SYSTEM, INCLUDING WIND RESISTING LIGHTWEIGHT METAL STUD SYSTEMS AND CONCRETE MASONRY WALLS
- NON-LOAD BEARING PARTITIONS
- ANY AND ALL GLASS, TOPPINGS AND FINISHES (WHETHER OR NOT THEY CONTAIN REINFORCING MATERIALS) NOT ATTACHED TO THE STRUCTURAL BUILDING FRAMEWORK NOR DEFINED ON THE STRUCTURAL DRAWINGS
- BUILDING SERVICES AND EQUIPMENT INCLUDING ANY AND ALL ELEMENTS AND THEIR SUPPORTING ACCESSORIES
- ELEVATING AND CONVEYING SYSTEMS
- ALL EMBEDDED OR SURFACE APPLIED CONNECTION MEANS NOT INTENDED TO SUPPORT A PORTION OF THE STRUCTURAL BUILDING FRAMEWORK

WHERE APPROPRIATE, THE DESIGN AND INSTALLATION OF SUCH ELEMENTS SHALL BE PROVIDED BY A PROFESSIONAL ENGINEER, LICENSED WITHIN THE RELEVANT JURISDICTION. AS THE STRUCTURAL DESIGNER, QUINN DRESSSEL ASSOCIATES IS NOT RESPONSIBLE FOR THE DESIGN OF SUCH ELEMENTS, NOR THE METHOD OR MEANS OF CONNECTING SUCH ELEMENTS TO THE BUILDING STRUCTURE.

NOTWITHSTANDING THE ABOVE, QUINN DRESSSEL ASSOCIATES SHALL HAVE SOLE DISCRETION TO REJECT ANY CONNECTION METHOD OR EMBEDDED ITEM WHICH WE JUDGE TO BE DETRIMENTAL TO THE PERFORMANCE OF THE STRUCTURAL BUILDING FRAMEWORK.

SHOP DRAWINGS

IT IS UNDERSTOOD AND ACKNOWLEDGED BY ALL THAT THE CO-ORDINATION AND PREPARATION OF THE SHOP DRAWINGS IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR, CONSTRUCTION MANAGER OR PROJECT MANAGER.

QUINN DRESSSEL ASSOCIATES WILL RECEIVE AND REVIEW, SHOP DRAWINGS PREPARED BY THE STRUCTURAL TRADES. SUCH REVIEW, IS FOR THE SOLE PURPOSE OF ASCERTAINING CONFORMANCE WITH THE GENERAL DESIGN CONCEPT, CRITERIA AND INTENT. TYPICALLY THIS WILL INCLUDE THE FOLLOWING:

- TEMPORARY EXCAVATION SHORING PLANS AND DETAILS
- CONCRETE FALSEWORK DRAWINGS
- REINFORCING STEEL SHOP DRAWINGS
- POST-TENSION PLANS AND DETAILS
- STRUCTURAL STEEL SHOP DRAWINGS
- METAL DECK SHOP DRAWINGS
- STEEL JOIST SHOP DRAWINGS
- STRUCTURAL PRE-CAST SHOP DRAWINGS

WHERE SO DIRECTED BY THE CONTRACT DOCUMENTS, THE ABOVE SUBMISSION MAY REQUIRE THE SEAL AND SIGNATURE OF A PROFESSIONAL ENGINEER, SO REGISTERED IN THE GOVERNING JURISDICTION. IN SUCH INSTANCES, THE SOLE RESPONSIBILITY FOR THE DESIGN OF SUCH ELEMENTS LIES WITH THAT DESIGNER AND IS OUTSIDE OF THE SCOPE OF SERVICES PROVIDED BY QUINN DRESSSEL ASSOCIATES. QUINN DRESSSEL ASSOCIATES WILL ALSO RECEIVE AND PROVIDE A LIMITED REVIEW OF SHOP DRAWINGS PREPARED BY TRADES OTHER THAN STRUCTURAL. SUCH REVIEW IS UNDERTAKEN SOLELY TO ASCERTAIN THE EFFECTS OF THE WORK OF OTHER TRADES UPON THE STRUCTURAL BUILDING FRAMEWORK, AND IS LIMITED TO A REVIEW OF THE LOADS AND MANNER IN WHICH THE LOADS ARE DELIVERED TO THE STRUCTURAL BUILDING FRAMEWORK. TYPICALLY, DRAWINGS PREPARED BY TRADES OTHER THAN STRUCTURAL WOULD INCLUDE:

- EXTERIOR BUILDING CLADDING SYSTEM, INDICATING LOADS AND ATTACHMENT METHODOLOGY
- SLEEVE DRAWINGS PREPARED BY THE MECHANICAL OR ELECTRICAL TRADES
- CORE REQUESTS BY THE MECHANICAL OR ELECTRICAL TRADES
- EQUIPMENT AND/OR PIPING LOADS AND ATTACHMENT METHODOLOGY
- WINDOW WASHING EQUIPMENT AND ANCHOR ATTACHMENTS

DRAWINGS RECEIVED WHICH DO NOT CONTAIN ADEQUATE LOADING INFORMATION WILL BE RETURNED AS "REJECTED". DRAWINGS WHICH ARE OF NO RELEVANCE TO A STRUCTURAL REVIEW WILL BE RETURNED AS "NO STRUCTURAL RELEVANCE - NOT REVIEWED".

RESPONSIBILITY FOR THE ADEQUACY AND SAFE OPERATION OF SUCH EQUIPMENT, ITS APPENDAGES, ANCHORAGES AND VARIOUS SUPPORTS MECHANISMS WHETHER APPLIED TO OR EMBEDDED WITHIN THE STRUCTURAL BUILDING FRAMEWORK IS THE SOLE RESPONSIBILITY OF ITS DESIGNER OR RELATED CONTRACTOR, AND IS NOT THE RESPONSIBILITY OF QUINN DRESSSEL ASSOCIATES.

B/ GENERAL

1. THE FOLLOWING GENERAL NOTES AND TYPICAL DETAILS SHOWN ON THE DRAWINGS ARE APPLICABLE TO ALL STRUCTURAL CONDITIONS NOT SPECIFICALLY DETAILED ON THE STRUCTURAL DRAWINGS.
2. THE STRUCTURAL DRAWINGS SHALL BE READ WITH THE SPECIFICATIONS AND OTHER CONTRACT DOCUMENTS. REFER TO THE ARCHITECTURAL DRAWINGS FOR FIRE SEPARATION REQUIREMENTS.
3. ONLY DIMENSIONS RELEVANT TO STRUCTURAL ELEMENTS ARE SHOWN ON THE STRUCTURAL DRAWINGS. FOR OTHER DIMENSIONS, AND LOCATIONS, SIZES OF SLEEVES OR FORMED OPENINGS NOT SHOWN, REFER TO OTHER CONTRACT DRAWINGS AND DOCUMENTS. OBTAIN THE ARCHITECTS PRIOR APPROVAL BEFORE INSTALLING SUCH OPENINGS, SLEEVES ETC.
4. SEE OTHER CONTRACT DRAWINGS FOR LOCATIONS AND DIMENSIONS OF PITS, BASES, SUMPS, TRENCHES, DEPRESSIONS, GROOVES, AND CHAMFERS NOT SHOWN ON STRUCTURAL DRAWINGS.
5. THE DESIGN LIVE LOAD SHOWN ON THE DRAWINGS SHALL NOT BE EXCEEDED DURING CONSTRUCTION. THE CONTRACTOR SHALL MAKE ADEQUATE PROVISIONS FOR CONSTRUCTION LOADS AND FOR ADEQUATE TEMPORARY BRACING TO KEEP ALL STRUCTURAL AND NON-STRUCTURAL ELEMENTS PLUMB AND IN TRUE ALIGNMENT AT ALL PHASES OF CONSTRUCTION.

C/ STANDARDS AND DESIGN CRITERIA

GENERAL

THIS BUILDING HAS BEEN DESIGNED IN ACCORDANCE WITH THE FOLLOWING CODES AND STANDARDS

OBC REG. 332/12

NBC 2015

CSA A23 SERIES

IMPORTANCE CATEGORY

THIS BUILDING HAS BEEN DESIGNED FOR AN IMPORTANCE CATEGORY OF NORMAL

DEAD LOADS

THE BUILDING HAS BEEN DESIGNED TO RESIST THE FOLLOWING DEAD LOADS. SPECIFIC DESIGN VALUES ARE REFERENCED ON INDIVIDUAL FRAMING PLANS.

- BUILDING SELF-WEIGHT
- WEIGHT OF ALL MATERIAL OF CONSTRUCTION INCORPORATED INTO THE BUILDING AND PERMANENTLY SUPPORTED THEREON.
- WEIGHT OF PARTITIONS, WHERE APPLICABLE
- VERTICAL GRAVITY LOADS DUE TO SOIL, PLANTING MATERIAL AND TREES.

LIVE LOADS

THE BUILDING HAS BEEN DESIGNED TO RESIST LIVE LOADS DUE TO USE AND OCCUPANCY. SPECIFIC DESIGN VALUES ARE REFERENCED ON INDIVIDUAL FRAMING PLANS. LIVE LOAD REDUCTIONS AS PERMITTED UNDER THE APPLICABLE GOVERNING CODE HAVE BEEN INCORPORATED INTO THE ELEMENT DESIGNS WHERE APPROPRIATE.

SNOW & RAIN

THE BUILDING'S ROOFS HAVE BEEN DESIGNED TO RESIST LOADS DUE TO SNOW AND RAIN AS DEFINED BY THE APPLICABLE CODE. THE FOLLOWING FACTORS ARE UNIQUE TO THIS BUILDING

Is (IMPORTANCE FACTOR)	=	1.00 (ULS)
Ss (1 IN 50 YEAR GROUND SNOW LOAD)	=	0.90 (SLS)
Sl (IN 50 YEAR ASSOCIATED RAIN LOAD)	=	1.1 kNm/m2
S (1 IN 50 YEAR ASSOCIATED RAIN LOAD)	=	0.4 kNm/m2

WIND

THE BUILDING HAS BEEN DESIGNED TO RESIST WIND FORCES AS CALCULATED IN ACCORDANCE WITH THE FOLLOWING FORMULA:

$P = IwqCeCp$	
WHERE Iw (IMPORTANCE FACTOR)	= 1.0 (ULS) (TABLE 4.1.7.1)
q (1 IN 50 YEAR REFERENCE VELOCITY PRESSURE)	= 0.75 (SLS) (TABLE 4.1.7.1)
Ce (BASED UPON $(open/rough)$ TERRAIN)	= 0.44 kPa
Cp (GUST EFFECT FACTOR) Cp (EXTERNAL PRESSURE COEFFICIENT)	= $(h/12)^{-1}$ BUT NOT LESS THAN 0.7
Ct (TOPOGRAPHIC FACTOR)	= 1.05 OR 1.3
	= 1.0

RESULTING OVERALL WIND DESIGN FORCES (FACTORED)

EAST-WEST		NORTH-SOUTH	
BASE SHEAR	80	BASE SHEAR	140
OVERTURNING MOMENT	540	OVERTURNING MOMENT	430

EXTERIOR ENVELOPE WIND LOADS

THE BUILDING'S EXTERIOR ENVELOPE SHALL BE DESIGNED TO RESIST WIND PRESSURES IN ACCORDANCE WITH THE ONTARIO BUILDING CODE. THE FOLLOWING DESIGN CRITERIA SHALL BE FOLLOWED BY THE ENVELOPE DESIGNER(S):

q	REFERENCE VELOCITY PRESSURE	=	0.44 kPa
Iw	IMPORTANCE FACTOR	=	1.0 (STRENGTH COMPLIANCE)
Ce	EXPOSURE FACTOR	=	0.75 (DEFLECTION COMPLIANCE)
		=	$(h/12)^{-1}$ BUT NOT LESS THAN 0.7

FOR EXTERNAL PRESSURES $Cp = Cq$ DETERMINED IN ACCORDANCE WITH FIGURE 4.1.7.6.B OBC 2012 (FOR VERTICAL CLADDING)

DETERMINED IN ACCORDANCE WITH FIGURE 4.1.7.6.C OBC 2012 (FOR HORIZONTAL ROOFING)

FOR INTERNAL PRESSURES Cp INTERNAL GUST FACTOR 2.0

Cq CATEGORY 2 - 0.45 to -0.3

(APPLIED TO FULL WALL AREAS) WALLS IN THE VICINITY OF MAJOR EXTERIOR OPENINGS MAY REQUIRE HIGHER VALUES.

EARTHQUAKE

SITE PROPERTIES:

SITE CLASS D (AS INDICATED IN GEOTECHNICAL REPORT NO. 22-094 R01 DATED MARCH 17, 2022 AND PREPARED BY CMT ENGINEERING INC. AND E-MAIL DATED MAY 31, 2022).

$PGA_{REF} = 0.0992$	
$PGA = 0.124$	$F(PGA) = 1.29$ (Table 4.1.8.4.H)
$Sa(0.2) = 0.193$	$F(0.2) = 1.24$ (Table 4.1.8.4.B)
$Sa(0.5) = 0.106$	$F(0.5) = 1.47$ (Table 4.1.8.4.C)
$Sa(1.0) = 0.056$	$F(1.0) = 1.55$ (Table 4.1.8.4.D)
$Sa(2.0) = 0.027$	$F(2.0) = 1.57$ (Table 4.1.8.4.E)
$Sa(5.0) = 0.0067$	$F(5.0) = 1.58$ (Table 4.1.8.4.F)
$Sa(10.0) = 0.0027$	$F(10.0) = 1.49$ (Table 4.1.8.4.G)

IMPORTANCE CATEGORY:

NORMAL $IE = 1.0$ (ULS)

INTERSTOREY DRIFT RATIO LIMITED TO 0.025%

STRUCTURAL CONFIGURATION:

IN ACCORDANCE WITH TABLE 4.1.8.6, THE BUILDING'S STRUCTURAL CONFIGURATION IS JUDGED TO BE "REGULAR" IN THE FOLLOWING CATEGORY(IES) TYPE

$IEFaSa(0.2) = 0.239 \times 0.35$

BUILDING HEIGHT = 9.4 m (30'-10")

Ta_{BASE} WEST DIRECTION = 0.25 s

Ta_{BASE} SOUTH DIRECTION = 0.25 s

ACCORDINGLY, THE EARTHQUAKE ANALYSIS HAS BEEN CARRIED OUT IN ACCORDANCE WITH THE "STATIC ANALYSIS PROCEDURE" AS DESCRIBED IN ARTICLE 4.1.8.7.

SEISMIC FORCE RESISTING SYSTEM (SFRS): CONVENTIONAL CONSTRUCTION - MASONRY SHEAR WALL AND TENSION-ONLY STEEL BRACING.

DESIGN FACTORS

Rd (DUCTILITY RELATED FORCE MODIFICATION FACTOR): = 1.5

Ro (OVER-STRENGTH RELATED FORCE MODIFICATION FACTOR): = 1.3

STATIC ANALYSIS PROCEDURE

MINIMUM LATERAL EARTHQUAKE FORCE $V = S(Ta)MwIEW/(RdRo) = 240$ kN

WHERE $Ta = 0.25$ s (ARTICLE 4.1.8.11.(3))

$S(Ta) = 0.225$ (Article 4.1.8.4.(9))

$Mw = 1.0$ (TABLE 4.1.8.11)


$J = 1.0$ (TABLE 4.1.8.11)

$W = 2900$ kN (DEAD LOAD+SUPERIMPOSED DEAD LOAD+0.25 SNOW LOAD AS DEFINED IN ARTICLE 4.1.8.2)

EAST-WEST		NORTH-SOUTH	
T_{SEA}	0.25	T_{SEA}	0.25
BASE SHEAR	240	BASE SHEAR	240
OVERTURNING MOMENT	1150	OVERTURNING MOMENT	1150

LATERAL FORCES ON BASEMENT WALLS:

- a. DESIGN OF THE BASEMENT WALLS RETAINING EARTH AND WATER HAS BEEN BASED ON THE LATERAL EARTH PRESSURE " p_h " GIVEN BY THE EXPRESSION:
 $p_h = k (w_h + h \cdot q)$ MULTIPLIED BY THE LOAD FACTOR 1.5
WHERE: $k = 0.50$
 $w_h = 22$ kN/m³ - UNIT WEIGHT OF EARTH
 $q =$ SURCHARGE OR ADJACENT FOOTING PRESSURE (kN/m²)
 $h =$ DEPTH OF SOIL FROM GRADE TO ROCK (m)
- b. IT IS ASSUMED THAT A FREE DRAINING SYSTEM SHALL BE INSTALLED, THEREFORE THE BASEMENT WALLS HAVE NOT BEEN DESIGNED TO RESIST ANY HYDROSTATIC PRESSURE.



D/ LATERAL LOAD RESISTING SYSTEM

THE LATERAL LOAD RESISTING SYSTEM FOR THE PROJECT IS CONVENTIONAL CONSTRUCTION MASONRY SHEAR WALL AND TENSION-ONLY STEEL BRACING.

E/ MATERIALS

1. CONCRETE

ELEMENT		EXPOSURE CLASS	MAX w/c RATIO	COMPRESSIVE STRENGTH	AIR ENTRAINMENT CATEGORY	CURING TYPE	CHLORIDE ION PENETRABILITY
--	--	A-XL	0.40	--	1 OR 2	3	< 1000 COULOMBS
--	--	A-1	0.40	--	1 OR 2	2	< 1500 COULOMBS
--	--	A-2	0.45	--	1	2	
--	--	A-3	0.50	--	2	1	
--	--	A-4	0.55	--	2	1	
--	--	C-XL	0.40	--	1 OR 2	3	< 1000 COULOMBS
--	--	C-1	0.40	--	1 OR 2	2	< 1500 COULOMBS
--	--	C-2	0.45	--	1	2	
--	--	C-3	0.50	--	2	1	
--	--	C-4	0.55	--	2	1	
--	--	F-1	0.50	--	1	2	
--	--	F-2	0.50	--	2	1	
--	FOOTING AND PIER	N	0.55	30		1	
--	--	N-CF	0.55	--		1	
--	--	R-1	0.55	--	2	1	
--	--	R-2	0.55	--	2	1	
--	--	R-3	0.55	--		1	
--	--	S-1	0.40	--	1 OR 2	2	
--	--	S-2	0.45	--	1 OR 2	2	
--	--	S-3	0.45	--	1 OR 2	1	

COMPRESSIVE STRENGTH f'_c IS THE ULTIMATE COMPRESSIVE STRENGTH AT :
28 DAYS FOR COMPRESSIVE STRENGTHS < 40 MPa
56 DAYS FOR COMPRESSIVE STRENGTHS > 40 MPa & < 55 MPa
90 DAYS FOR COMPRESSIVE STRENGTHS > 55 MPa

OTHER REQUIREMENTS

REFER TO THE PROJECT SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS. EMBEDDED ITEMS WITHIN THE CONCRETE ELEMENTS SHALL ADHERE TO THE REQUIREMENTS OF CSA 413-21 AND EITHER BE NON-METALLIC, HIGH SILICON CAST IRON, STAINLESS STEEL OR SUITABLY PROTECTED COATED AGAINST CORROSIVE EFFECTS. EXPOSED ITEMS WITHIN THE CHLORIDE PROTECTION ZONE (CPZ) SHALL BE EITHER STAINLESS STEEL OR SUITABLY PROTECTED BY GALVANISING OR OTHER DURABLE COATING.

2. REINFORCING STEEL

TYPE	f_y - MIN. YIELD STRENGTH (MPa)	REMARKS
WELDED WIRE FABRIC	400	
DEFORMED REINFORCING STEEL	400	

ALL REINFORCING STEEL TO CONFORM TO CSA G30.18 - 21

3. STRUCTURAL STEEL

DESIGNATION	TYPE	YIELD STRENGTH (MPa)	MIN. TENSILE STRENGTH (MPa)
G40.21	350W	350	450

HSS MEMBER CONFORMING TO CSA G40.20 CLASS C. FOR OTHER MATERIALS, SEE SPECIFICATIONS.

F/ FOUNDATION

1. THE LINE OF SLOPE BETWEEN ADJACENT FOOTINGS OR EXCAVATIONS OR ALONG STEPPED FOOTINGS SHALL NOT EXCEED A RISE OF 7 IN A RUN OF 10. FOR FOUNDATION DESIGN PARAMETERS REFER TO GEOTECHNICAL REPORT #22-094.R01 PREPARED BY CMT ENGINEERING INC. DATED MAR. 17, 2022, FOR BEARING CAPACITIES = 150 kPa (SLS).
2. PREVENT SOIL ADJACENT TO AND BENEATH ALL FOOTINGS FROM FREEZING. PLACE ALL EXTERIOR FOOTINGS A MINIMUM OF 1200mm BELOW FINISHED GRADE.
3. FOOTING EXCAVATIONS AND CAISSON BASES SHALL BE INSPECTED AND CERTIFIED IN WRITING BY A QUALIFIED GEOTECHNICAL ENGINEER BEFORE ANY CONCRETE IS PLACED.
4. DO NOT PLACE BACKFILL AGAINST WALLS RETAINING EARTH, OTHER THAN CANTILEVERED WALLS, UNTIL THE FLOOR SLABS AT TOP AND BOTTOM OF THE WALLS ARE POURED AND CURED.
5. CARRY OUT BACKFILLING AGAINST FOUNDATION WALLS WHICH HAVE EARTH ON BOTH SIDES IN SUCH A MANNER THAT THE LEVEL OF BACKFILLING ON ONE SIDE OF THE WALL IS NEVER MORE THAN 450mm DIFFERENT FROM THE LEVEL ON THE OTHER SIDE OF THE WALL.
6. IF SPECIFIED CONCRETE STRENGTH FOR COLUMNS AND WALL IS DIFFERENT AND THEY ARE POURED MONOLITHICALLY, THEN THEY SHALL HAVE THE GREATER CONCRETE STRENGTH OF EITHER STRUCTURAL MEMBER.

G/ SLAB ON GRADE

1. PLACE SLAB ON GRADE ON MATERIAL CAPABLE OF SUSTAINING 24 kNm/m² WITHOUT SETTLEMENT RELATIVE TO THE BUILDING FOUNDATIONS.
2. FOR THICKNESS OF SLAB ON GRADE SEE FOUNDATION PLAN. MAINTAIN SLAB THICKNESS AT ALL DEPRESSIONS. SEE ARCHITECTURAL DRAWINGS FOR LOCATION AND EXTENT OF FINISHES AND DEPRESSIONS.
3. UNLESS NOTED ON PLAN OTHERWISE, PROVIDE A MINIMUM OF WELDED WIRE FABRIC REINFORCING 152x152 X MW18.7xMW18.7.
4. REFER TO C/ STANDARDS & DESIGN CRITERIA FOR PROTECTION SYSTEM DESIGNATION.

REVISIONS / ISSUE

NO.	DATE	
1	2025-05-21	ISSUED FOR PERMIT
2	2025-07-16	ISSUED FOR UPDATES

DISCLAIMER:

CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS. ANY DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECT PRIOR TO PROCEEDING WITH THE WORK. DRAWINGS ARE NOT TO BE SCALED.

"ALL DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS ARE THE COPYRIGHTED PROPERTY OF THE ARCHITECT AND MUST BE RETURNED UPON REQUEST. REPRODUCTION OF DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS IN PART OR WHOLE IS FORBIDDEN WITHOUT THE ARCHITECT'S WRITTEN PERMISSION."

NOTIFY ARCHITECT OF ANY DISCREPANCIES AND WAIT FOR INSTRUCTION PRIOR TO PROCEEDING WITH WORK.



Quinn Dressel
ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS



paradigm
architecture + design
2198 Gerard St E Toronto ON M4E 2C7
[t] 416.686.3624 www.paradigm-ad.com

STAMP:



PROJECT NAME / LOCATION:

**100071257 ONTARIO LTD.
BUILDING RENOVATION**

**78 ADVANCE RD,
ETOBICOKE, ON, M8Z 2T7**

DRAWING TITLE:

GENERAL NOTES

DRAWN BY: **MH** PROJECT NO.: **24-327**

CHECKED BY: **RY** SCALE: **N.T.S.**

DATE: **2025-07-16**

DRAWING NO.: **S101**

H/ CONCRETE AND REINFORCING

1. CLEAR CONCRETE COVER TO REINFORCING

CLEAR COVER IS THE DISTANCE MEASURED FROM THE CONCRETE SURFACE TO THE NEAREST BAR DEFORMATION. MINIMUM COVER DIMENSION IS DEPENDANT UPON THE EXPOSURE CLASS OF CONCRETE AS INDICATED IN THE TABLE BELOW

CLEAR CONCRETE COVER TO BARS			
EXPOSURE CONDITION	N, N-CF, R-3	F1, F-2, S-1, S-2, S-3, R-1, R-2	C-XL, A-XL, C-1, C-3, A-1, A-2, A-3
CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH	75mm	75mm	75mm
BEAMS, GIRDERS	30mm	40mm	60mm
TIED REINFORCEMENT WITHIN WALLS AND COLUMNS	40mm	40mm	60mm
SLAB, WALLS, JOISTS, SHELLS AND FOLDED PLATES	25mm	40mm	60mm
NOMINAL RATIO OF COVER TO NOMINAL BAR DIAMETER (mm)	10 15 20 25 30 35	10 15 20 25 30 35	10 15 20 25 30 35
NOMINAL RATIO OF COVER TO NOMINAL AGGREGATE SIZE (ASSUMES 19mm AGGREGATE)	19mm	29mm	38mm

FOR COVER REQUIREMENTS IN AREAS OF THE BUILDING THAT ARE PART OF A CHLORIDE PROTECTION ZONE (CPZ) REFER TO TABLE BELOW.

IN ACCORDANCE WITH OBC-MMMH SUPPLEMENTARY STANDARDS SB-2, THE ABOVE VALUES WILL PROVIDE SUFFICIENT COVER TO PROVIDE MINIMUM 2 HOUR FIRE PROTECTION TO THESE ELEMENTS WHERE SO INDICATED ON THE ARCHITECTURAL DRAWINGS. IN AREAS WHERE FIRE SEPARATION REQUIREMENTS EXCEED 2 HOURS, INCREASED VALUES OF COVER MAY APPLY.

CHLORIDE PROTECTION SYSTEM DESIGNATION	TOP COVER			BOTTOM COVER
	DEFORMED BARS & WWF		POST TENSION SHEATH/DUCT	
	EXPOSURE CONDITION			
	NORMAL EXPOSURE	SEVERE EXPOSURE		
MI	40	40	60	30
MX	40	40	60	30
M	40	45	60	30
IX	40	45	60	30
IS	45	50	60	30
I	50	55	60	30
XS	55	60	60	30
X	60	65	60	30

2. MINIMUM CLEAR DISTANCE BETWEEN PARALLEL BARS SHALL BE THE GREATEST OF THE FOLLOWING:
- 1.4 BAR DIAMETER
 - 1.4 TIMES MAXIMUM SIZE OF AGGREGATE
 - 30mm MINIMUM
- WHERE PARALLEL REINFORCEMENT IS TO BE PLACED IN MULTIPLE LEVELS, THE BARS SHALL BE PLACED DIRECTLY ABOVE EACH OTHER TO FACILITATE THE FLOW OF CONCRETE AROUND THE BARS.
3. MINIMUM LAPS OF CONTINUOUS DEFORMED BARS SHALL BE 24 Ø OR 450mm WHICHEVER IS GREATER. LAPS OF WELDED WIRE FABRIC SHALL BE 150mm AT ENDS AND EDGES. INCREASE LAPS BY 20% FOR EPOXY COATED BARS.
4. ALL DOWELS SHALL HAVE A MINIMUM EMBEDMENT OF 24 Ø OR 450mm MINIMUM, EXCEPT THAT DOWELS TO SLAB SHALL HAVE A MINIMUM EMBEDMENT OF 600mm. INCREASE LAP LENGTHS BY 20% FOR EPOXY COATED BARS.

REFER TO THE FOLLOWING TABLES FOR DEVELOPMENT & SPLICE LENGTHS AND MINIMUM BAR EMBEDMENTS.

WHERE PARALLEL REINFORCEMENT IS TO BE PLACED IN MULTIPLE LEVELS, THE BARS SHALL BE PLACED DIRECTLY ABOVE EACH OTHER TO FACILITATE THE FLOW OF CONCRETE AROUND THE BARS.

DEVELOPMENT OF STRAIGHT DEFORMED BARS IN COMPRESSION

CONCRETE STRENGTH	BAR LOCATION	BAR SIZE					
		10M	15M	20M	25M	30M	35M
20 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	350	420	550	650	770
25 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	310	380	490	580	690
30 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	360	450	530	630
35 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
40 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
45 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
50 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
55 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
60 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
65 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
70 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
75 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630
80 MPa	CONFINED ZONES WITHIN TIES OR SPIRALS	200	290	350	450	530	630
	OTHER	200	290	350	450	530	630

USE OF THE ABOVE TABLE ASSUMES THE FOLLOWING:

REINFORCING STEEL GRADE 400 MPa

- A. COMPRESSION MEMBER WITH 10M TIES SPACED 100mm OR LESS, OR
- B. COMPRESSION MEMBER WITH 6M SPIRALS SPACED 100mm OR LESS

DEVELOPMENT OF STRAIGHT DEFORMED BARS IN TENSION

CONCRETE STRENGTH	BAR LOCATION	BAR SIZE					
		10M	15M	20M	25M	30M	35M
20 MPa	> 300mm CONC BELOW HORIZ BAR	480	670	820	1330	1570	1870
	OTHER	370	520	630	1020	1210	1440
25 MPa	> 300mm CONC BELOW HORIZ BAR	430	600	740	1190	1400	1670
	OTHER	330	460	570	910	1080	1290
30 MPa	> 300mm CONC BELOW HORIZ BAR	390	550	670	1080	1280	1530
	OTHER	300	420	520	830	990	1180
35 MPa	> 300mm CONC BELOW HORIZ BAR	360	510	620	1000	1190	1420
	OTHER	300	390	480	770	910	1090
40 MPa	> 300mm CONC BELOW HORIZ BAR	340	480	580	940	1110	1330
	OTHER	300	370	450	720	850	1020
45 MPa	> 300mm CONC BELOW HORIZ BAR	320	450	550	890	1050	1250
	OTHER	300	350	420	680	810	960

USE OF THE ABOVE TABLE ASSUMES THE FOLLOWING:

REINFORCING STEEL GRADE 400 MPa

NORMAL DENSITY CONCRETE

UNCOATED BARS

BARS ARE WITHIN A

A. COMPRESSION MEMBER WITH TIES

B. BEAMS WITH STIRRUPS, OR

C. SLABS OR WALLS WITH CLEAR SPACING AT LEAST TWO BAR DIAMETERS WITH COVER GREATER THAN OR EQUAL TO ONE BAR DIAMETER

DEVELOPMENT OF HOOKED DEFORMED BARS IN TENSION Idh

CONCRETE STRENGTH	BAR LOCATION	BAR SIZE/OUTER BEND RADIUS					
		10M 45mm	15M 65mm	20M 80mm	25M 100mm	30M 155mm	35M 185mm
20 MPa	CONFINED ZONES WITHIN TIES	150	200	250	320	380	450
	OTHER	180	250	310	400	470	560
25 MPa	CONFINED ZONES WITHIN TIES	150	180	220	290	340	400
	OTHER	160	230	280	360	420	500
30 MPa	CONFINED ZONES WITHIN TIES	150	170	200	260	310	370
	OTHER	150	210	250	330	390	460
35 MPa	CONFINED ZONES WITHIN TIES	150	160	190	240	290	340
	OTHER	150	190	240	300	360	430
40 MPa	CONFINED ZONES WITHIN TIES	150	150	180	230	270	320
	OTHER	150	180	220	280	340	400
45 MPa	CONFINED ZONES WITHIN TIES	150	150	170	220	250	300
	OTHER	150	170	210	270	320	380


USE OF THE ABOVE TABLE ASSUMES THE FOLLOWING:

REINFORCING STEEL GRADE 400 MPa

NORMAL DENSITY CONCRETE

UNCOATED BARS

BARS PLACED WITHIN MINIMUM 60mm SIDE COVER AND 50mm END COVER



ROOF UPLIFT DIAGRAM

NOTES:

1. UNFACTORED WIND UPLIFT FORCE (1m² TRIBUTARY AREA; EXTERIOR PLUS INTERIOR FORCE)

- ZONE C = 1.85 kPa ↑
- ZONE S = 0.96 kPa ↑
- ZONE R = 0.74 kPa ↑

REVISIONS / ISSUE

NO.	DATE	
1	2025-05-21	ISSUED FOR PERMIT
2	2025-07-16	ISSUED FOR UPDATES

DISCLAIMER:

CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS. ANY DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECT PRIOR TO PROCEEDING WITH THE WORK. DRAWINGS ARE NOT TO BE SCALED.

"ALL DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS ARE THE COPYRIGHTED PROPERTY OF THE ARCHITECT AND MUST BE RETURNED UPON REQUEST. REPRODUCTION OF DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS IN PART OR WHOLE IS FORBIDDEN WITHOUT THE ARCHITECT'S WRITTEN PERMISSION."

NOTIFY ARCHITECT OF ANY DISCREPANCIES AND WAIT FOR INSTRUCTION PRIOR TO PROCEEDING WITH WORK.



Quinn Dressel
ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS



paradigm
architecture + design
2198 Gerrard St E Toronto ON M4E 2C7
[t] 416.698.3624 www.paradigm-ad.com

STAMP:



PROJECT NAME / LOCATION:

**100071257 ONTARIO LTD.
BUILDING RENOVATION**

**78 ADVANCE RD,
ETOBICOKE, ON, M8Z 2T7**

DRAWING TITLE:

GENERAL NOTES

DRAWN BY: **TP** PROJECT NO.: **24-327**


CHECKED BY: **RY** SCALE: **N.T.S.**



DATE: **2025-07-16**

DRAWING NO.:

S102





TD402	ELEVATOR DIVIDER BEAM CONNECTION 2L-100x100x10 HORIZONTAL SLOTTED HOLES SLOTTED HOLES IN BEAM KWIK BOLTS or EQUAL CENTER LINE of BOLTS PLAN 1-1 METHOD "A" 150 wide POCKET 100 250 150 wide HOLE 100 FILL IN WITH EXPANDING DRY-PACK GROUT AFTER S200 IN PLACE WELD TO RESIST ELEVATOR FORCES DOOR SIDE FLOOR SILL SUPPORT ANGLE BY OTHER L150x100x10 CLIPx150 long 2-24x6x200 long STRAPS METHOD "B" NOTE: METHOD "B" CAN BE USED ONLY IF CONCRETE WALL ABOVE FLOOR AND IF ELEVATOR MANUFACTURER DOOR DETAILS PERMIT.
TD403	ANCHORAGE FOR STEEL STAIR TO CONCRETE SLAB STAIR STRINGERS 100 FLOOR OR LANDING L150x100x8 CONTINUOUS OR L150x100x8 x 250 LG. WITH 2-25x6 x 250 LG. STRAPS TOP AND BOTTOM AT EACH STRINGER 25x6 x 250 LG. STRAPS @600 o/c TOP AND BOTTOM STAGGERED
TD01	TYPICAL SLAB REPAIR AT NEW UNDERGROUND SERVICES 1 SITE VERIFY NEW CONCRETE SLAB ON U-FILL. REPAIR ANY EXISTING MOISTURE BARRIER IF FOUND. SAW CUT SLAB CHIP 1"x4" WEDGE @ 2'-0" o/c EXIST. CONCRETE SLAB ON GRADE 10M@24" DRILL & GROUT WHILT HIT-HY 200 ADHESIVE MIN. EMBED 1/4" LAP-BARS 3" MIN. EXTENT OF EXCAVATION NEW BURIED SERVICE BY G.C. REPLACE SUB-GRADE WITH U-FILL CONCRETE 2'-0" MIN. 1" 3" 3" 6" MAX. NOTE: 1. COORDINATE WITH ARCH & MECH DWGS FOR THE PIPING ROUTE AND DEPTH. 2. SCAN FOR ANY POSSIBLE EMBEDDED SERVICES WITHIN/BELOW THE EXISTING SLAB ON GRADE PRIOR TO ANY SAW CUTTING. 3. NEW SUBGRADE MATERIAL TO BE U-FILL 5 MPa CONCRETE 4. NEW SLAB ON FILL SHALL BE 20MPa CONCRETE FINISHED TO ACCEPT SEAMLESS FLOOR FINISH.
TD506	DECK SUPPORT AT COLUMNS EDGE OF DECK L-75x75x8 FLUSH WITH BOTTOM OF DECK BY STEEL CONTRACTOR 6 100 250 PERIMETER COLUMN INTERIOR COLUMN
TD02	HOUSKEEPING PAD TYPICAL DETAIL EQUIPMENT FINISH FLOOR EXIST S.O.G. PROVIDE 10M BENT DOWELS AS SHOWN - DRILLED & EPOXIED INTO SLAB. DOWELS TO BE 400W REBAR. START WITH 1 SET OF DOWELS AT CORNERS (4" IN FROM EDGE) & MAX. 18" SPACING AT EACH DIRECTION. 4" THICK CONCRETE HOUSKEEPING PAD, MIN f'c=25 MPa (TO MATCH STRENGTH OF EXISTS S.O.G.) 152x152 MM 18.7x18.7 WWF 1 LAYER INSTALLED AT MID-DEPTH OF HOUSKEEPING PAD 18" MAX. 4" ± @ TWO DIRECTION 1" 6" 1" NOTE: COORDINATE WITH CONSULTANTS FOR UNIT LOCATION AND SIZE.

REVISIONS / ISSUE		
NO.	DATE	
1	2025-05-21	ISSUED FOR PERMIT
2	2025-07-16	ISSUED FOR UPDATES
DISCLAIMER CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS. ANY DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECT PRIOR TO PROCEEDING WITH THE WORK. DRAWINGS ARE NOT TO BE SCALED. "ALL DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS ARE THE COPYRIGHTED PROPERTY OF THE ARCHITECT AND MUST BE RETURNED UPON REQUEST. REPRODUCTION OF DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS IN PART OR WHOLE IS FORBIDDEN WITHOUT THE ARCHITECT'S WRITTEN PERMISSION." NOTIFY ARCHITECT OF ANY DISCREPANCIES AND WAIT FOR INSTRUCTION PRIOR TO PROCEEDING WITH WORK.		
  Quinn Dressel ASSOCIATES CONSULTING STRUCTURAL ENGINEERS  FLAT IRON BUILDING GROUP  paradigm architecture + design [t] 416.686.3624 www.paradigm-ad.com STAMP:  PROJECT NAME / LOCATION: 100071257 ONTARIO LTD. BUILDING RENOVATION 78 ADVANCE RD, ETOBICOKE, ON, M8Z 2T7 DRAWING TITLE: TYPICAL DETAILS DRAWN BY: MH CHECKED BY: RY PROJECT NO.: 24-327 SCALE: N.T.S. DATE: 2025-07-16 DRAWING NO.: S103		




REVISIONS / ISSUE		
NO.	DATE	
1	2025-05-21	ISSUED FOR PERMIT
2	2025-07-16	ISSUED FOR UPDATES
DISCLAIMER: CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS. ANY DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECT PRIOR TO PROCEEDING WITH THE WORK. DRAWINGS ARE NOT TO BE SCALED. "ALL DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS ARE THE COPYRIGHTED PROPERTY OF THE ARCHITECT AND MUST BE RETURNED UPON REQUEST. REPRODUCTION OF DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS IN PART OR WHOLE IS FORBIDDEN WITHOUT THE ARCHITECT'S WRITTEN PERMISSION." NOTIFY ARCHITECT OF ANY DISCREPANCIES AND WAIT FOR INSTRUCTION PRIOR TO PROCEEDING WITH WORK.		
		
 Quinn Dressel ASSOCIATES CONSULTING STRUCTURAL ENGINEERS		
 FLAT IRON BUILDING GROUP		
 paradigm architecture + design 2198 Gerrard St E Toronto ON M4E 2C7 [t] 416.686.3624 www.paradigm-ad.com		
STAMP: 		
PROJECT NAME / LOCATION: 100071257 ONTARIO LTD. BUILDING RENOVATION 78 ADVANCE RD, ETOBICOKE, ON, M6Z 2T7		
DRAWING TITLE: EXISTING BUILDING SECTIONS		
DRAWN BY: MH		PROJECT NO.: 24-327
CHECKED BY: RY		SCALE: As indicated
		DATE: 2025-07-16
		DRAWING NO.: S152

2025-11-03 1:52:05 PM
Project Drafting\24-4757D QDA Drafting 24-327 Works for Structural 78 Adv Rd, Toronto\Working



ALL EXISTING INFORMATION SHOWN ON DRAWINGS IS TRANSFERRED FROM EXISTING BASE BUILDING DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE TO SITE VERIFY THE ACCURACY OF THESE DOCUMENTS WITH AS-BUILT CONDITIONS. ALL DETERMINATION OF EXISTING CONDITIONS MUST BE MADE PRIOR TO ANY STRUCTURAL DEMOLITION. ALL DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECTS OR ENGINEERS.

S153



1 ROOF FRAMING PLAN
S201 1/8" = 1'-0"

*** DENOTES: PROVIDE SEPARATE PRICE

- NOTES:
- TOP OF EX. JOIST AT EL. 13'-4". TOP OF STEEL AT EL. 13'-1".
 - EXTERIOR GREEN ROOF ON EXISTING WOOD ROOF LOADS:
SUPERIMPOSED DEAD LOAD
SLAB SELF WEIGHT = 0.5 kPa
CEILING AND MECHANICAL = 0.3 kPa
SUPERIMPOSED LIVE LOAD = 1.6 kPa
SNOW LOAD-ACCUMULATION(SEE PLAN) = 1.28 kPa

NEW INTERIOR RECREATION AREA ON EXISTING WOOD ROOF LOADS:
SUPERIMPOSED DEAD LOAD
SLAB SELF WEIGHT = 0.2 kPa
CEILING AND MECHANICAL = 0.3 kPa
PARTITION = 0.7 kPa
SUPERIMPOSED LIVE LOAD = 2.4 kPa
 - REFER TO ARCHITECTURAL DRAWINGS FOR THE FOLLOWING INFORMATION:
a) ALL FINISHED FLOOR ELEVATIONS
b) LOCATION AND POSITION IN PLAN OF ALL
i) CHANGES IN ELEVATION
ii) SLAB OPENING'S SIZE AND LOCATION
iii) WALL LOCATIONS
c) BUILT UP FLOOR ASSEMBLY
 - INSERTS FOR THE ATTACHMENT OF NON-STRUCTURAL ITEMS ARE TO BE SUPPLIED BY THE NON-STRUCTURAL TRADE INVOLVED. LOCATION AND PLACEMENT WITHIN THE CONCRETE STRUCTURE SHALL NOT DISPLACE REINFORCEMENT STEEL. ALL INSERTS NOT SATISFACTORY TO QUINN DRESSSEL ASSOCIATES WILL BE REMOVED AT NO COST.
 - SHOP DRAWINGS, SLEEVING DRAWINGS, CONDUIT LAYOUT DRAWINGS AND THE LIKE SHALL ACCURATELY INDICATE THE SIZE, LOCATION AND EXTENT OF SUCH ITEMS. ALL SUCH DRAWINGS SHALL BE SUBMITTED TO THE CONSULTANTS MINIMUM 4 WEEKS PRIOR TO CONCRETE SLAB POURS.
 - REFER TO THE FOLLOWING DRAWING SERIES FOR RELATED INFORMATION:
S100 SERIES - GENERAL NOTES AND TYPICAL DETAILS
S300 SERIES - COLUMN & FOOTING SCHEDULES
S400 SERIES - FOUNDATION SECTIONS & DETAILS
S500 SERIES - WALL ELEVATIONS
 - ALL EXTERIOR STRUCTURAL STEEL SHALL BE HOT GALVANIZED.
 - ADD 1/4" BENT CLOSURE PLATES TYPICAL WHERE NECESSARY.
 - REFER TO ARCH FOR BUILT UP FLOOR ASSEMBLY. BUILT UP FLOOR EXTENTS SHOWN ON PLAN AS SHADED GRAY.

ALL EXISTING INFORMATION SHOWN ON DRAWINGS IS TRANSFERRED FROM EXISTING BASE BUILDING DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE TO SITE VERIFY THE ACCURACY OF THESE DOCUMENTS WITH AS-BUILT CONDITIONS. ALL DETERMINATION OF EXISTING CONDITIONS MUST BE MADE PRIOR TO ANY STRUCTURAL DEMOLITION. ALL DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECTS OR ENGINEERS.

REVISIONS / ISSUE		
NO.	DATE	ISSUED FOR PERMIT
1	2025-05-21	ISSUED FOR PERMIT
2	2025-07-16	ISSUED FOR UPDATES

DISCLAIMER:
CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS. ANY DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECT PRIOR TO PROCEEDING WITH THE WORK. DRAWINGS ARE NOT TO BE SCALED.

"ALL DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS ARE THE COPYRIGHTED PROPERTY OF THE ARCHITECT AND MUST BE RETURNED UPON REQUEST. REPRODUCTION OF DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS IN PART OR WHOLE IS FORBIDDEN WITHOUT THE ARCHITECT'S WRITTEN PERMISSION."

NOTIFY ARCHITECT OF ANY DISCREPANCIES AND WAIT FOR INSTRUCTION PRIOR TO PROCEEDING WITH WORK.

2198 Gerard St E Toronto ON M4E 2C7
[t] 416.688.3624 www.paradigm-ad.com

STAMP:





PROJECT NAME / LOCATION:
100071257 ONTARIO LTD. BUILDING RENOVATION

78 ADVANCE RD,
ETOBICOKE, ON, M8Z 2T7

DRAWING TITLE:
SECOND FLOOR FRAMING PLAN




DRAWN BY: MH	PROJECT NO.: 24-327
CHECKED BY: RY	SCALE: As indicated
	DATE: 2025-07-16
	DRAWING NO.: S201



2025-11-03 1:52:12 PM
C:\Users\ry\OneDrive\Documents\100071257\100071257_24-327_2nd Floor Framing Plan.dwg
R:\Projects\100071257\100071257_24-327_2nd Floor Framing Plan.dwg







REVISIONS / ISSUE		
NO.	DATE	
1	2025-05-21	ISSUED FOR PERMIT
2	2025-07-16	ISSUED FOR UPDATES
3	2025-10-22	ISSUED FOR UPDATES

NOTIFY ARCHITECT OF ANY DISCREPANCIES AND WAIT FOR INSTRUCTION PRIOR TO PROCEEDING WITH WORK.





7 SECTION
S404 3/4" = 1'-0"



- ALL EXISTING INFORMATION SHOWN ON DRAWINGS. IS TRANSFERRED FROM EXISTING BASE BUILDING DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE TO SITE VERIFY THE ACCURACY OF THESE DOCUMENTS WITH AS-BUILT CONDITIONS. ALL DETERMINATION OF EXISTING CONDITIONS MUST BE MADE PRIOR TO ANY STRUCTURAL DEMOLITION. ALL DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECTS OR ENGINEERS.

REVISIONS / ISSUE		
NO.	DATE	
1	2024-06-11	ISSUED FOR CLIENT'S REVIEW
2	2024-07-24	ISSUED FOR PERMIT
3	2024-08-24	ISSUED FOR TENDER
4	2025-07-16	ISSUED FOR UPDATES



Quinn Dressel
ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS



paradigm
architecture + design
2198 Gerrard St E Toronto ON M4E 2C7
[t] 416.686.3624 www.paradigm-ad.com

STAMP:



PROJECT NAME / LOCATION:

100071257 ONTARIO LTD.
BUILDING RENOVATION

78 ADVANCE RD,
ETOBICOKE, ON, M8Z 2T7

DRAWING TITLE:

**SECOND FLOOR / LOWER
ROOF SECTIONS III**






DRAWN BY:	PROJECT NO.:
DP	24-327

CHECKED BY:	SCALE:
BY	As indicated

DATE: 2025-07-16

DRAWING NO.:

S404



ALL EXISTING INFORMATION SHOWN ON DRAWINGS IS TRANSFERRED FROM EXISTING BASE BUILDING DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE TO SITE VERIFY THE ACCURACY OF THESE DOCUMENTS WITH AS-BUILT CONDITIONS. ALL DETERMINATION OF EXISTING CONDITIONS MUST BE MADE PRIOR TO ANY STRUCTURAL DEMOLITION. ALL DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECTS OR ENGINEERS.

S501